

**No. Advt/KC/2019/04/(a)**  
**KARIMGANJ COLLEGE**  
**KARIMGANJ**

**Date: 07/03/2019**

**Name of work:** Providing R.C.C. slab in Chemistry Laboratory of Karimganj College.

Item no	Description of work	Quantity	Unit
1/18 1.1	Supplying fitting and fixing reinforcement bars (b) other ISI TM.	1.65 QH	/QH
2/3.1.1 3.1.15	Providing form work of timber Planking. Flat surface (II) 25 mm thick.	53.65 <sup>2</sup> m	/m <sup>2</sup>
3/2.2.1	Providing and laying R.C.C. work. (N) (b) M-20 or 1:1:5:3	2.70 <sup>3</sup> m	/m <sup>3</sup>
4/4.1.8	a) 1 <sup>st</sup> class brick nagged wall. b) 75 mm thick (b) 1:4.	21.70 <sup>2</sup> m	/m <sup>2</sup>
5/5.7.1.1	Providing ceramic floor tiles (a) Normal Range 1) 300 x 300 m.	97.05 <sup>2</sup> m	/m <sup>2</sup>
TOTAL Rs			1,26,117.00
Add 7.5% for G.S.T. Rs			9463.00
G.Total			1,35,640.00
<b>Say Rs 1, 35,700.00</b> <b>(Rupees One lakh thirty five thousand seven hundred) only.</b>			



**Principal,  
Karimganj College**

**No. Advt/KC/2019/04/(b)**  
**KARIMGANJ COLLEGE**  
**KARIMGANJ**

**Date: 07/02/2019**

**Name of work:** Estimate for washing in Physics building at Karimganj College (inside).

<b>Item no</b>	<b>Description of work</b>	
1/13.2.2(f)	Distemper with dry distemping of approve brand and manufacture (two coats) and of required shade etc. comp. Area $2 \times 58.50 \times 3.60 = 417.60 \text{ m}^2$ $8 \times 2 \times 7.00 \times 3.60 = 403.20 \text{ m}^2$ <b>Deduct opening-</b> Door- $1 \times 15 \times 2.10 \times 1.20 = (-)75.60 \text{ m}^2$ Window- $1 \times 29 \times 1.20 \times 1.00 = (-)34.80 \text{ m}^2$ $710.40 \text{ m}^2$	
3/13.6.6	Painting one coat on old wood based surface. (i) surface over 100 mm in width/girth (ii) High gloss Asian paint/ Berger paint.  Area = $108.90 \text{ m}^2$	
<b>Total</b>		<b>68,878.00</b>
<b>Say Rs 69,000.00</b> <b>(Rs sixty nine thousand)</b>		

The rates of this estimate are as per APWD SOR for 2013-14.




**Principal,  
Karimganj College**

**No.Advt/KC/2019/04/(c)**  
**KARIMGANJ COLLEGE**  
**KARIMGANJ**

**Date: 15/02/2017**

**Name of work:** Improvement of approach road from College field to boys' hostel building at Karimganj College.

Item no	Description of work	Quantity	Unit
1/21 1.1	Providing cast in situ manually driven C.C. Pile@ dia 250 mm.	54.00 Pi	/Pi
2/18.11	Supplying fitting and fixing in position of reinforcement bars 10 mm Q.T.S.	8.01 QHS	/QHS
	(C) M.S. rod 6 mm Q	2.97 QHS	/QHS
3/1.4	a) Rising low site around the building (b) other than Guwahati city.	137.28 m <sup>3</sup>	/m <sup>3</sup>
4/3.11	Providing form 3.1.1.1 with foundation, footing (b) 25 mm thick	5.40 m <sup>2</sup>	/m <sup>2</sup>
3.1.12	Sides of the beam (b) 25 mm thick	57.60 m <sup>2</sup>	/m <sup>2</sup>
3.1.1.3	Column, Pillar, Post etc. (b) 25 mm thick	10.80 m <sup>2</sup>	/m <sup>2</sup>
5/2.2.1	C.C. in RCC works @ Ms-15	5.54 m <sup>3</sup>	/m <sup>3</sup>
6/4.1.4	Brick work in cement 1) self-structure (b) 1:4	12.90 m <sup>3</sup>	/m <sup>3</sup>
7/2.11	Plain cement Concrete works b) 1:4:8	16.84 m <sup>3</sup>	/m <sup>3</sup>
<b>TOTAL</b>			3,16,116.00
8	Misc. items such as carrying of Rubsish and setting in a/road.	L/S	14,000.00
TOTAL Rs			3,30,116.00
<b>Say Rs 3, 30, 000.00</b> <b>(Rupees Three Lakh thirty thousand) only.</b>			

  
**Principal,**  
**Karimganj College**



# KARIMGANJ COLLEGE

ESTD. - 1946

P.O. & DIST. KARIMGANJ :: ASSAM, Pin- 788710

website : <http://www.karimganjcollege.ac.in>

E-mail : [karimganjcollege@gmail.com](mailto:karimganjcollege@gmail.com)

Phone : (03843) 262108 (O) Fax : (03843) 267043

Dr. Mrinal Kanti Bhattacharya  
M.Sc., LL.B., Ph.D.

PRINCIPAL

Ref. No. ....

Date : .....

No: Advt/KC/2019/4/e

## Advanced Institutional Biotech Hub, Karimganj College

Specifications for the supply of gas and gas cylinders

1.	Nitrogen + Hydrogen +CO <sub>2</sub> Mixture Gas (80:10:10)	7.0m <sup>3</sup>
2	UHP Nitrogen Gas	7.00m <sup>3</sup>
3	Mix Gas Cylinder (46.7 ltrs WC)	1
4	Nitrogen Gas Cylinder (46.7 ltrs WC)	1
5	Branded Regulator for Hydrogen Gas	1
6	Branded Regulator for Nitrogen Gas	1

Principal,  
Karimganj College



**No. Advt/KC/2019/04/(d)**  
**KARIMGANJ COLLEGE**  
**KARIMGANJ**

**Date: 08/03/2019**

**Name of work:** Washing and painting in the Chemistry building (inside) at Karimganj College.

<b>Item no</b>	<b>Description of work</b>	<b>Quantity</b>	<b>Unit</b>
1/13 1.1	Removing white or Colour washing	525.00 <sup>2</sup> m	/m <sup>2</sup>
2/13 2.2	(m) Distempering two coats with Oil bound distemper(III) top coat	525.00 <sup>2</sup> m	/m <sup>2</sup>
	DO		
	(1) Priming Coat	525.00 <sup>2</sup> m	/m <sup>2</sup>
3/ 6.5	Painting two coats on new/old wood based surface(1)	127.00 <sup>2</sup> m	/m <sup>2</sup>
TOTAL Rs			58,693.00
Add 7.5% for G.S.T. Rs			4,401.00
G.Total			63,094.00
<b>Say Rs 63,000.00</b> <b>(Rupees Sixty Three Thousand) only.</b>			

  
**Principal,**  
**Karimganj College**